ROYALTY CALCULATION

Name of Work : Construction and repairs to culverts in Dasarahalli Ward no 15

Plain Cement Concrete 1:3:6			
Description	Qty in Cum	Constant	Total Qty
Sand	15.39	0.46	7.08
Jelly	15.39	0.89	13.70
M20 concrete			
Description	Qty in Cum	Constant	Total Qty
Sand	77.70	0.43	33.41
Jelly	77.70	0.69	53.61
Precast concrete slab			
Sand	1.74	0.459	0.80
Jelly	1.74	0.878	1.53

Sl	Items	Qty	Rate	Amount
1	Sand	41.29	103.00 126	4253.00 5203
2	Jelly	68.84	108.00 138	7434.00 9500
			Total	11687.00 14703

Asst.Engineer
Dasarahalli Ward No 15

Asst.Executive Engineer
T.Dasarahalli Sub Division

Scanned by CamScanner